## **EROSION AND SEDIMENT CONTROL NOTES:**

#### 1. GENERAL MEASURES

- SCHPICKAL MEASURES
   STOCKPILES SHALL BE CONFINED TO ONE CENTRAL AREA WHERE POSSIBLE.
   EROSION CONTROL MEASURES TO BE IN PLACE PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION WORK. MEASURES ARE APPLIED TO PROTECT ADJOINING PROPERTIES FROM EROSION AND SILT DAMAGE.
   EROSION CONTROL MEASURES NOT TO BE REMOVED UNTIL CONSTRUCTION IS

- EROSION CONTROL MEASURES NOT TO BE REMOVED UNTIL CONSTRUCTION IS COMPLETED AND SITE HAS BEEN REHABILITATED.
   REHABILITATION INCLUDES COMPLETION OF ALL CONSTRUCTION WORK AND LANDSCAPING, SEEDING OR TURFING OF ALL BATTERS AND FILL AREAS.
   PIPED DRAINAGE NETWORKS SHOULD BE INSTALLED AND CONNECTED AS EARLY
- AS POSSIBLE.

   ALL AREAS NOT SUBJECT TO CONSTRUCTION WORKS SHALL BE RETAINED FREE FROM DISTURBANCE OR DAMAGE DURING THE CURRENCY OF THE CONTRACT.
  SHOULD THESE AREAS BECOME DISTURBED OR DAMAGED, THEY SHALL BE
- RE-INSTATED BY THE CONTRACTOR AT NO COST TO THE PRINCIPAL.

  WHERE SAWCUTTING IS CARRIED OUT THE POLLUTED WATER SHALL BE INTERCEPTED AS CLOSE AS POSSIBLE TO THE CONSTRUCTION SITE AND REMOVE BY A VACUUM DEVICE.

# 2. STABILIZATION OF DISTURBED AREAS. - STABILIZATION OF DISTURBED AREAS SHALL BE IN ACCORDANCE WITH


- COUNCIL'S SPECIFICATION FOR GRASSING AND/OR SPECIFICATION FOR LANDSCAPE WORKS. THE FOLLOWING SHALL BE APPLIED FOR THE CONTROL OF EROSION AND SEDIMENTATION:-
- (a) STABILIZATION OF DENUDED AREAS SHALL COMMENCE AS SOON AS POSSIBLE AFTER THE AREAS HAVE BEEN DISTURBED.
- (b) ALL STABILIZATION MEASURES SHALL BE UNDERTAKEN PRIOR TO THE END OF THE MAINTENANCE PERIOD.


### 3. MAINTENANCE


- ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE MAINTAINED IN A SATISFACTORY WORKING ORDER THROUGHOUT THE CONTRACT, MAINTENANCE AND DEFECTS LIABILITY PERIODS OR UNTIL SUCH EARLIER TIME AS THE AREA HAS BEEN STABILIZED AND THE SUPERINTENDENT DIRECTS THAT THE DEVICE BE
- THE CONTRACTOR SHALL INSPECT ALL DEVICES AFTER EACH STORM FOR STRUCTURAL DAMAGE OR CLOGGING BY SILT AND OTHER DEBRIS AND MAKE PROMPT REPAIRS OR REPLACEMENT.


## 4. SEDIMENT CONTROL DEVICES (S.C.D.)


- THESE SHALL BE CONSTRUCTED AT INLETS TO STORMWATER SYSTEMS TO TRAP THE SEDIMENT IN RUNOFF. SECTIONS 11.3.02/03/04/06 OF THE N.S.W. DEPARTMENT OF HOUSING CONSTRUCTION SPECIFICATION, 1989 EDITION, SHALL




















(ORIGINAL = A3 SHEET)

CHECKED & APPROVED	SURVEYED & DRAFTED QUANTITIES	SERVICES AFFECTED	S.R.A. / SURV. GEN.		SERVICES	DATUM				INNER WEST COUNCIL	FILE NO.	SHEET NO.
5.0			R.T.A.		TELECOM/OPTUS —T—T—T—T—	A 11 B				INNER WEST COUNCIL		
			A.G.L. / SHELL PIPELINES		GAS —G—G—G—	A. H. D.						
The second second	DESIGNED		SYDNEY WATER		SEWER —S—S—S—	SCALES				STANDARD ENVIRONMENTAL DRAWING — E1	PLAN NO.	
ADDRESS SON CONCERNICATION	PG/DJT		TELSTRA / OPTUS		WATER —W—W—W—					STANDARD ENVIRONMENTAL DRAWING - ET		-4 I
APPROVED FOR CONSTRUCTION	MAY 2019 INNER WES	Ti ·	SYDNEY ELECTRICITY		RAILWAY —R—R—R—R—	l NA				SEDIMENT & EROSION CONTROL PLAN	6	<u> </u>
			NOTICE OF ENTRY		ELEC. CABLES —E—E—E—	NA NA				SEDIMENT & ENOSIGN CONTROL FLAN		
	PG/DJT COUNCIL		KERB & GUTTER		OIL PIPELINES —P—P—P—						.,===:	u <b>V1</b>
ACC.	MAY 2019	1	NOTICES	DATE	STORM WATER —SW—SW—SW—		AMEND DATE	DESCRIPTION	APPROV.		VERSION	, VI